BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18325/CALL-2

APPROVED SCHEDULE - B

EE/B[illegible]P/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Patching pot holes in main and cross roads of Balaji layout, Maruthinagara, BB nagara, Sahakaranagara B, C and D block, shanthinikethana and surrounding areas in ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of H V MADAN KUMAR		
				In Figures		In Words
1	907.04	Scarifying stone metal crust 50 to 100 mmthick with pick azxes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all labour charges complete as per specification	sqm	50.0	45352.00	Rupees Fifty Only
2	181.41	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with pave	cum	1710.15	310238.31	Rupees One Thousand Seven Hundred Ten and Fifteen Paise Only
3	907.04	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excav	sqm	344.4	312384.58	Rupees Three Hundred Forty Four and Forty Paise Only
					667974.89	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/2/16